

# Transformer-less Unified Power Flow Controller for Wind and Solar Power Transmission

Presenter(s): Fang Z. Peng, and Shuitao Yang

January 21, 2015

# Project Objectives

---

## Overall Goals

- To develop and demonstrate a transformer-less UPFC

## Uniqueness

- Unique Topology: cascaded multi-level inverters to eliminate transformers
- Scalability and modularity: the same basic blocks to reach any power levels

## Challenges

- To achieve superior power flow control for the entire range
- To eliminate active power flow to CMLs and maintain DC voltage

## Problems of the Traditional Technology

- Back-to-back inverters required
- No back-to-back connection possible for CMLs

## Performance Metrics

- Low cost (\$0.05/VA), light weight (1000 lbs/MVA)
- High efficiency (>99%) and fast dynamic response (<5 ms)


## Key Outcomes

A working prototype of a 2-MVA transformer-less UPFC system

# 3rd Year Accomplishments

- Q9:** ▶ UPFC functionality test at low voltage level (4,160 V)
  - ▶ System modulation, control and protection software developed
  - ▶ 15-kV lab design, and construction
- Q10:** ▶ UPFC installation to the 15-kV high voltage lab
- Q11:** ▶ System for 13.8-kV/2 MVA UPFC demonstration configured
  - ▶ Functional test with all shunt and series CMI sub-modules
- Q12:** ▶ Initial UPFC test results at 13.8-kV, independent P/Q control and dc  
voltage balancing control implemented
  - ▶ Testing data collected and analyzed



# Michigan UP Grid Scenario




- Loop flow problem: Power demand is high on south and east side of Lake Michigan. But, some power finds its way through high impedance path in the UP.
- Eastern UP grid is “split” from that of West UP in order to prevent overloading of lines/equipment and to eliminate under voltage. UP split is necessary for 95% time of a year.
- Difficult to perform scheduled maintenance, to regulate voltage in eastern UP
- LP disconnected from UP due to high phase shifting requirement

Sankar, et. al, “ATC’S MACKINAC BACK-TO-BACK HVDC PROJECT: PLANNING AND OPERATION CONSIDERATIONS FOR MICHIGAN’S EASTERN UPPER AND NORTHERN LOWER PENINSULAS”, CIGRE’ 2013 Grid of the future Symposium

# Michigan UP Grid Solutions Investigated




- Building new lines. New lines could not solve the problem, other measures (power flow control) were needed.
- Back-to-back HVDC intertie of west and east UP: cost prohibited, rejected by the committee
- Limited solution: Connecting UP and LP through HVDC to implement partial power flow control
- **No UPFC solutions have been investigated**



Sankar, et. al, "ATC'S MACKINAC BACK-TO-BACK HVDC PROJECT: PLANNING AND OPERATION CONSIDERATIONS FOR MICHIGAN'S EASTERN UPPER AND NORTHERN LOWER PENINSULAS", CIGRE' 2013 Grid of the future Symposium

# Michigan UP Grid Solutions

## Currently used Solution: HVDC to tie UP and LP




**Back-to-Back MMC-VSC**  
**Device Power Rating = 4 pu**

**4x System Rating**

- Full control over power flow (200MVA/100Mvar)
- Cost of power converter = \$90 Million\*\* !
- Cost of overall project = \$130 Million\* !

\*St. Ignace news report, \*\* ABB Press Release

## Proposed Solution 1: UPFC to the optimal site Solution 2: UPFC to tie UP and LP



**Cascade Multilevel Inverter (CMI)**  
**Device Power Rating = 0.5-1 pu**  
**For  $\pm 30^\circ$  or  $60^\circ$  phase shifting**

**(0.5-1)x System Rating**  
**8x smaller device**

- Full control over power flow (200MVA/100Mvar)
- Cost of Power Converter = \$11-22M ?
- Cost of overall project = ?

# 2 MVA DEMONSTRATION






**13.8 KV, 2 MVA PROTOTYPE**  
**INVERTER MODULES** { 12 SERIES  
30 SHUNT

**BASE MODULE**  
**(100A / 200A)**

# UPFC Test Results at 13.8 kV


Final Year  
Accomplishments



13.8 kV UPFC Test Setup and Experimental Waveforms


# UPFC Test Results at 13.8 kV

Final Year  
Accomplishments



# UPFC Test Results at 13.8 kV

Final Year  
Accomplishments




## Key Challenges Remaining:

- Pilot test/ demonstration of the UPFC at 15-kV level and 2 MVA rating
- System reliability, bypass and line fault protection


## New Findings:

- DC capacitor energy of each CMI to increase network **inertia**.
- Only a fraction of the system rating is needed for all UPFC functions.


The maximum voltage,  $V_{c,max}$  in the series CMIs and the maximum current,  $I_{p,max}$  in the shunt CMIs are **0.2** and **0.4 pu**, respectively.



Equipment cost



Investment cost



- On the IEEE 300 Bus system, the optimal placements and parameters are:

No. of years	Location	UPFC (pu)	Invest (M)	Benefit (M)
1	121-119	0.138	\$0.555	\$11.14
5	191-225	1.595	\$6.382	\$79.91
10	191-225	1.595	\$6.382	\$166.2

## SUBSEQUENT INVESTMENT STUDY (5 YEAR BASE)

Investment Period	Location	UPFC (pu)	Invest (M)	Benefit (M)
1	191-225	1.5954	\$6.382	\$79.91
2	121-119	0.1187	\$0.474	\$66.63
3	242-245	0.0101	\$0.04	\$10.13

# Near-term Plans

---

## Key commercial challenges to date:

- Uncertain capital funding flow to sustain product development efforts beyond ARPA-E.
- Strong inertia and risk-averse culture of power industry (i.e. utility and vendors-alike).
- Securing real-world demonstration partners for technology.

## Upcoming commercial activities:

- Currently talking to a couple of interested companies to explore a pilot project.
- Talking to investors to set up a startup.

# Post ARPA-E Goals

---

- **Immediate Post-ARPA-E plan**
  - Upgrade of prototype to a product
  - Validation of all protection functions to demonstrate reliability
  - Technology transfer of the Transformer-less UPFC
  - Demonstration of the Transformer-less UPFC technology
- **Resources to be expected**
  - Investors
  - Utility companies
  - Governmental agencies

# Conclusions

---

- A cost-effective power flow control device has been developed.
- The new UPFC is modular, scalable, reliable, compact, lightweight, and highly efficient.
- The new UPFC can control voltage, compensate impedance, and shift phase angle, which has been verified experimentally.
- Large-scale test cases were used for study of:
  - Cost saving through congestion reduction;
  - Hourly dispatch for power flow control;
  - Reduction of loop flows;
  - Increase of wind power injection.