

Developing an Ultra-Compact, Topology-Optimized Heat Exchanger using Additive Manufacturing

Ram Ranjan, Raytheon Technologies Research Center

Project Vision

By integrating advanced design methods with physics-based AM process models, we have demonstrated an ultra-compact, fully optimized 50 kW heat exchanger.

10X smaller than SOA, 40X more durable than SOA

Brief Project Overview


Fed. funding:	\$2.2M
Length	33 mo.



Team member	Location	Key Personnel	Role in project
Raytheon Technologies Research Center	East Hartford, CT	Dr. Ram Ranjan, Dr. Katie Kirsch, Dr. Paul Attridge, Mr. Alex Cadar, Mr. Bob Dold, Dr. Joe Turney	Project lead, HX design, process modeling, and fabrication
RunToSolve, LLC	Baltimore, MD	Dr. James Guest	HX design optimization
University of Wisconsin Madison	Madison, WI	Dr. Mark Anderson	HX testing

Context/history of the project

- RTRC and RTS have participated in prior ARPA-E programs.
- RTRC has been developing additive HXs for propulsion applications over the last decade.




Progress Against Tasks



	Major Tasks and Go / No-Gos
Critical Risk Reduction 9 months	Task 1: HX Design & Requirements
	Go / No-Go: HX design completion for FOA targets
Sub-scale HX Demonstration 12 months (complete June 2021)	Task 2: AM process modeling & sub-scale fabrication
	Task 3: Material and HX coupon testing
	Go / No-Go: Sub-scale HX Testing Completion & Performance
Full-scale HX Demonstration 12 months (End May 2022)	Task 4: Full scale HX design, fabrication, testing
	Task 5: Technology to Market
	Task 6: Program Management (TRL/MRL Review)

Heat Exchanger Design Summary

- ▶ Novel aspects compared to the state of the art
 - Novel core geometries that survive high pressure conditions
 - Topology optimized features in the header and core to improve performance
- ▶ Performance metrics
 - > 10 kW/kg (full HX power density), $dP < 2\%$ of inlet pressure, $> 10,000$ hr durability, $< \$200$ /kW
- ▶ Risks progression
 - Design risk for structural performance reduced, material property and build quality proven at sub-scale level, manufacturing scale risk undergoing reduction



Counter-flow topology optimized configurations



Self-supporting structures created during optimization process based on build direction

Custom topology optimization tools, high fidelity flow, thermal, and stress analysis

Material Selection and Property Testing


► Material update

- Haynes 282 tensile and creep property measurements completed
 - Tensile properties up to 900 C within +10% of published wrought properties
 - Creep strength slightly inferior (within -10%) to published wrought data

► Material properties with additive

- Property testing provided confidence in HX survivability and durability prediction
- Exposure to sCO2 and its impact on material composition similar to wrought samples

Creep Strength vs. Use Temp. and Duration



**Data on Haynes 282 creep strength taken from MatWeb




Sample 22
RT




Sample 50
900C

Failure more brittle at high temperature

— Time = 3600000 s 1000 hr — Time = 360000 s 100 hr



AM H282 Sample




Bulk H282 Sample

Oxide layer thickness is similar between AM and bulk

sCO2 exposure autoclave testing

Manufacturing Process Development

- ▶ Manufacturing process
 - Additive manufacturing (laser bed powder fusion)
 - Design freedom more than conventional process but AM constraints increase design cycle time
 - ~100% density, microstructure (dendritic solidification and elongated grains)



- ▶ Manufacturing risk reduction
 - Coupon, features and full sub-scale HX fabricated
 - Microstructure and creep properties at elevated temperatures and thin features investigated



Testing Progress and Plan




WisCO₂ Loop Capabilities

$$\dot{m} = 0.015 - 0.8 \text{ kg/s}$$

$$P = 1000 - 3600 \text{ psi}$$



$$T \leq 800^\circ\text{C} \text{ (at Test HX)}$$



Test loop for recuperator testing:
Completed sub-scale HX testing in Q2 of 2021

Fabrication of Prototype Heat Exchangers and Testing


10 kW HX successfully tested in Q2, 2021 at full program conditions



Test setup at University of Wisconsin at Madison

Hot Inlet
 $T=799.5 \pm 1.5 \text{ C}$
 $P=8.23 \pm 0.06 \text{ MPa}$

Cold Outlet
 $T=7xx \text{ C}$
 $P=24.8x \text{ MPa}$



Cold Inlet
 $T=301.8 \pm 1.5 \text{ C}$
 $P=24.84 \pm 0.07 \text{ MPa}$

Hot Outlet
 $T=3xx \text{ C}$
 $P=8.2x \text{ MPa}$

Experimental results from 10 kW sCO₂ HX test at HITEMMP full program conditions


Measure heat transfer (10 kW) within 3% of predictions/design

dP < 0.2% of inlet pressure on both sides

Risks

All program major risks reduced through design-build-test iterations

Risk	#
Structural requirements not met	1
Fluid leakage	2
AM post processing	3
Cost too high	4
Scalability	5



X Now
 X Start of project

Q & A



U.S. DEPARTMENT OF
ENERGY

<https://arpa-e.energy.gov>