




Hyperefficient Data Centers for Deep Decarbonization of Large-scale Computing

Saeed Moghaddam, U. of Florida

COOLERCHIPS Annual
Meeting
December 11 & 12, 2024

Total Project Cost:	\$3M
Length	36 mo.


Brief COOLERCHIPS Project Overview

Team member	Location	Role in project, core competencies
University of Florida	Gainesville, FL	Lead, heat sink and system design and integration
Boyd Corporation	Laconia, NH	Manufacturing, liquid cooling and phase change
University of Maryland	College Park, MD	Reliability assessment
NREL	Golden, CO	Packaging and DC-level testing
TRINA	Ann Arbor, MI	Thermomechanical Analysis


Project Vision

- 126 kW rack with 1000 W chips operating @ 40 °C ambient, with ~70 °C exit primary loop temperature
 - Enabled by a unique water phase-change heat sink
- Reducing TCO while providing high quality waste heat for heating (space and water) and cooling (via operating heat-driven chillers)
 - Particularly attractive for EDGE computing


Objective



Conventional Air-cooled DC



Innovation




* Data collected at $T_{\text{sat}} = 55^\circ\text{C}$ (increases to $\sim 1800\text{ W/cm}^2$ @ $T_{\text{sat}} = 100^\circ\text{C}$)
 - All 2Φ heat sinks operating at $T_{\text{sat}} < 60^\circ\text{C}$.

TTV Design and Manufacturing



(A) TTV bond pads



(B) TTV underside



(C) Placing TTVs and reflowing in furnace





Suhas Tamvada
Postdoctoral Associate
Organization: UF



Chaitanya Bathina
Postdoctoral Associate
Organization: UF

3 kW Experimental System

- ▶ Testing in thermosyphon configuration




Suhas Tamvada
Postdoctoral Associate
Organization: UF




Zihan Hu
Graduate Student
Organization: UF

Heat Sink Performance




$$T_{\text{chip}} - T_{\text{fluid}} = \sim 6 \pm 0.35^{\circ}\text{C} @ 1000 \text{ W Chip}$$







Integrated Server and Rack CDU Solution

- ▶ Completed two-phase rack level cooling solution using 50 – 55 C water from dry cooler
 - ✓ Tested manifold technology for coolant delivery to servers
 - ✓ Tested NCG management technology for reliable system operation at sub-ambient pressure
 - ✓ Tested in-rack condenser cooling capacity for >120 kW cooling



10kW Scale Condenser Testing

- ▶ The images on the left show substantial initial NCG in the system
- ✓ Images on the right demonstrate that NCG has been eliminated
- ✓ Measured cooling capacity meets performance target




11/18/2024

11/22/2024


IR Images show the back side of the condenser exposed to the vapor

Technoeconomic Analysis


100 MW Data Center PUE & Cooling Systems
Average Power Consumption



100 MW Data Center Cooling Solution Initial Cost and
Operating Cost By Technology



Cooling Solution Annual Operating Cost \$ / kW IT




Jerome Toth
Sr. Vice President, Eng. & Tech.
Organization: Boyd



Sukhvinder Kang
Chief Technology Officer
Organization: Boyd

System Configuration



COOLERCHIPS Program



EDGE Computing (Utilizing Waste Heat)



10 kW Server Design & Manufacturing



Mechanical Analysis & Reliability





Fig. 11: System Availability Model



Eric Dede
Title: Director, ERD
Organization: TRINA



Paul Paret
Title: Sr. Res. Eng.
Organization: NREL




Gilbert Moreno
Sr. Res. Eng.
Organization: NREL



Patrick McCluskey
Professor
Organization: UMD

Schedule

Year 1
(chip/ server-level
integration)



Year 2
(Rack-level integration/
validation)



Year 3
(Demonstration at
data center)



Reliability assessment, enhancement, modeling, Digital Twin (DT)

Technoeconomic modeling

Test Case: NVIDIA AI Technology Center at UF (NVAITC-UF)



- 3.2 MW, PUE ~ 1.6, serving Florida higher education institutions
- First in North America; a joint research center of NVIDIA and UF for advancing Artificial Intelligence (AI) education and research, as well as fostering partnership between higher education and industry.

Value Proposition:

- Eliminates the chiller plant and AHUs
 - Account for ~50% of facility footprint
- Higher server density per rack reduces white space by ~70%
 - Replace 40 (~40 KW) racks by 13 racks
- No water use in cooling towers
- Zero GWP coolant
- Silent operation
- > 70% of waste heat can be recovered and reused for district heating (when possible) or operating heat-driven chillers
 - Currently HPs are used to elevate temperature from ~30 °C to 60-80 °C, depending on system requirements and climate.

Q & A




U.S. DEPARTMENT OF
ENERGY

saeedmog@ufl.edu

Market Opportunities (EDGE Computing – heat reuse)



MGH Gray Building: Heating and Cooling



Energy consumption associated with HVAC system in Massachusetts General Hospital (MGH) Gray building

Technology to Market (T2M) Plan

- Finalize reliability and failure models, cost/ performance models, marketing collateral
 - Market demand survey, adoption challenge and opportunity analysis
- Business plan for Board approval
 - Technoeconomic analysis, value proposition, risk analysis
 - Required capital and ROI analysis
 - Materials and components Supply Chain analysis
 - Manufacturing ramp & scaling analysis
 - FIT models and insurance, warranty, and service cost analysis
- Regulatory
 - Safety compliance testing and certifications