Group C: Automated Cable Splicing Breakout Session (Wednesday, July 20th at 9:40am ET)

Reminder!!

Respond to Polling Questions:

- **1.** Scan the QR code using your mobile device or;
- **2.** Type the following link into any web browser:

bit.ly/3o3HWXI





Is it necessary to develop new splice designs in order to enable machineassisted splicing? What could a new splice or accessory look like?



Is aiming for a 70% decrease in total man hours per splice, a 50% reduction in total splicing time, and a >98% success rate (based on 'to be established' pass/fail criteria) in a 3-year project (average ARPA-E project timeline) a reasonable target? Are there any other potential metrics we should consider (please be specific and quantitative)?



How should we test a newly completed splice in order to improve the reliability and hence effectively extend the service life of an underground power system? How is it tested today?



Would machine-assisted splicing potentially change the requirements for the underground joining box (manhole-vault)? To what extent could this result in a reduction in the size of such underground space?



Is aiming for semi-automated, single-core to single-core cable splicing (using a nominal cable discussed during the Day 1 breakout session) too easy/reasonable/aggressive in a 3-year R&D project (average ARPA-E project timeline)? What are some of the most recent technological improvements in underground MV cable splicing (e.g. 3-phase main feeder with solid-state dielectric)?



What are the typical steps involved (both above ground crews and underground crews) in underground power cable splicing?



What are the top three priority technologies in need of research funding to transform today's power cable splicing?

- a) new splice design,
- b) advanced manual tools,
- c) automated splicing,
- d) sensors/diagnostic tools,
- e) Others (please describe)



What are the top three priority technologies in need of research funding to transform today's power cable splicing?

- a) new splice design,
- b) advanced manual tools,
- c) automated splicing,
- d) sensors/diagnostic tools,
- e) Others (please describe)



Approximately how many total man hours are required today to splice a 3-phase underground main feeder?

- a) 5-10 hours
- b) 10 20 hours
- c) 20 30 hours
- d) Over 40 hours



Which parts of the splicing process could be automated to reduce errors?

- a) Ground and check continuity
- b) Remove jacket, semiconductor, & insulations layers
- c) Prep ground shield
- d) Prep conductors
- e) Install splice
- f) Crimp conductors
- g) Insulate conductors
- h) Connect ground shields
- i) Insulate ground shields
- j) Check integrity of splice
- k) Others (please describe)



How frequently does a new splice in an existing underground power distribution circuit need to be replaced if they are installed correctly?

- a) 10 years
- b) 50 years
- c) 100 years
- d) Other?____



What is the greatest value for utility companies to automate splicing and reduce errors in underground cable insulation? (rank or select multiple)

- a) Increased worker safety by lowering total man hours spent in the manhole
- b) Reduce the overall number of man hours required to enhance splicing efficiency
- c) Increase splicing quality by performing some processes with a machine capable of executing jobs with great accuracy and reproducibility
- d) Enhance cable splice reliability by implementing advanced on-site inspection after each splicing job
- e) Extend the overall service life of subterranean assets
- f) Other values (please describe)

